



NOTES:

1. CONCRETE SHALL BE PLACED 10' UPSTREAM FROM EVERY MANHOLE. ADDITIONAL CONCRETE COLLAR LOCATIONS INCLUDE ON EITHER SIDE OF A STREAM/DITCH LINE OR UPON RECOMMENDATIONS OF THE CITY OF PORTLAND UTILITY DEPARTMENT.
2. CONCRETE COLLAR SHALL PERTRUDE INTO NATIVE SOIL A MINIMUM OF 12" ON BOTTOM AND SIDE OF TRENCH AND EXTEND TO A MINIMUM OF 1' BELOW THE SURFACE ELEVATION.

CONCRETE COLLAR

N.T.S.



CITY OF PORTLAND  
DEPARTMENT OF UTILITIES – SEWER  
STANDARD SEWER DETAILS

REVISION NO: 1  
DATE: 06/01/2021

WW-09